

DORFP No. 1 for JOC CONTRACT 2020003 (.01 - .05)
CITY OF BUCKEYE
CONSTRUCTION & CONTRACTING DIVISION

ADDENDUM No. 6

NOTE: Attach to Original DORFP. However, if Proposal has already been returned, complete this amendment and return for attachment to your Proposal by 3:00 p.m., MST, January 27, 2022.

City of Buckeye
530 East Monroe Avenue
Buckeye, Arizona 85326
Attn: pglasmann@buckeyeaz.gov

SOLICITATION: DORFP No. 1: Verrado Way – Yuma Road to Van Buren Street Intersection Improvements

NOTICE TO CONTRACTORS:

This Addendum forms a part of the Contract and clarifies, corrects, or modifies the original Delivery Order Request for Proposal documents prepared by the City of Buckeye.

Bid Due Date and Time: January 27, 2022, no later than 3:00 p.m., MST

THE FOLLOWING QUESTIONS WERE ASKED BY CONTRACTORS:

Q1. Are we able to close the intersection of Yuma and Verrado for paving?

A1. No, not completely – school is there.

Q2. Can a bid item for 4 each internally illuminated signs be added to the bid schedule?

A2. Yes, added in the revised Schedule of Values dated 1/6/22 (attached).

Q3. Is the shotcrete channel incidental to bid item 36, Construct Headwall Per COB Std Dtl 51200?

A3. No, shotcrete added to revised Schedule of Values dated 1/6/22 (attached).

Q4. Per Addendum #5, Asphalt Pavement and Aggregate Base Class 2 has a quantity of 0. Is this correct?

A4. No, a formula off to the side that was removed was tied to those lines – it has been corrected (See revised Schedule of Values dated 1/6/22 attached).

Q5. Bid item 13, Safety Rail has a quantity of 1 EA on SOV, however it cannot be found on the plans. Please advise.

A5. Current plans have safety rail. Safety rail is to City of Buckeye standard exists in multiple locations. 250' has been verified and put in the revised Schedule of Values dated 1/6/22 (attached).

NOTE: Please be sure to use the correct Schedule of Values when submitting your bids – which is the revised Schedule of Values dated 1/6/22 (attached). Thank you.

The balance of the specifications and instructions remain the same. Offerors must acknowledge receipt and acceptance of this amendment by returning the entire Addendum with the Delivery Order Request for Proposals.

PLEASE ACKNOWLEDGE YOUR FIRM'S RECEIPT OF THIS AMENDMENT BY SIGNING THE ATTACHED SOLICITATION AMENDMENT ACKNOWLEDGEMENT.

SOLICITATION AMENDMENT ACKNOWLEDGEMENT

DORFP No. 1: Verrado Way – Yuma Road to Van Buren Street Intersection Improvements

ADDENDUM No. 6

ADDENDUM ISSUE DATE: January 6, 2022

Offeror certifies that Offeror has read, understands, and will fully and faithfully comply with this Delivery Order Request for Proposals, its attachments and any referenced documents. Offeror also certifies that this offer was independently developed without consultation with any of the other Offerors or potential Offerors.

Name of Company: _____

Authorized Signature: _____

Print Name and Title: _____

Date: _____

Address: _____

City, State, Zip Code: _____

Telephone Number: _____

Email Address: _____

City of Buckeye

Intersection Improvement -Verrado Way and Yuma Road

Item No.	Item Description	Unit	Quantity	Price	Amount
1	REMOVE EXISTING ASPHALT PAVEMENT (2' MIN)	SY	19740		\$0.00
2	REMOVE CONCRETE CURB AND GUTTER	LF	265		\$0.00
3	REMOVE DIRECTIONAL RAMP	SY	60		\$0.00
4	REMOVE POLE AND FOUNDATIONS	EA	1		\$0.00
5	REMOVE ASPHALT SIDEWALK	SF	3820		\$0.00
6	ASPHALT CONCRETE PAVEMENT	TON	9011		\$0.00
7	CONSTRUCT ASPHALT PAVEMENT EDGE TYPE A PER MAG STD DTL 201	LF	3430		\$0.00
8	CONSTRUCT DIRECTIONAL RAMPS, PER COB STD DTL 63240	EA	6		\$0.00
9	CONSTRUCT VERTICAL CURB AND GUTTER PER MAG STD DTL 220-1 TYPE "A"	LF	4555		\$0.00
10	CONSTRUCT SINGLE CURB TERMINATION, PER MAG STD DTL 222.	EA	14		\$0.00
11	INSTALL SAFETY RAIL PER COB STD DTL B-110	LF	250		\$0.00
12	INSTALL TRASH RACK PER COB STD DTL B-508	EA	2		\$0.00
13	CONSTRUCT CONCRETE SIDEWALK, PER COB STD DTL 230	SF	3,330		\$0.00
14	ADJUST WATER VALVE BOX TO GRADE PER MAG STD DTL 391-2	EA	5		\$0.00
15	ADJUST MANHOLE FRAME AND COVER TO GRADE, PER MAG STD DTL 422	EA	7		\$0.00
16	ADJUST TRAFFIC SIGNAL PULLBOX TO GRADE	EA	3		\$0.00
17	CONSTRUCT PASS THROUGH CURB PER DETAIL ON SHEET 25	EA	3		\$0.00
18	POLE (TYPE A)	EA	2		\$0.00
19	POLE FOUNDATION (TYPE A)	EA	2		\$0.00
20	POLE (PEDESTRIAN POST)	EA	4		\$0.00
21	POLE FOUNDATION (PEDESTRIAN POST)	EA	4		\$0.00
22	ELECTRICAL CONDUIT (2") (PVC)	LF	170		\$0.00
23	TRAFFIC SIGNAL FACE (TYPE R)	EA	4		\$0.00
24	TRAFFIC SIGNAL MOUNTING ASSEMBLY (TYPE V)	EA	2		\$0.00
25	TRAFFIC SIGNAL MOUNTING ASSEMBLY (TYPE VI)	EA	2		\$0.00
26	TRAFFIC SIGNAL MOUNTING ASSEMBLY (TYPE II)	EA	2		\$0.00
27	PEDESTRIAN CROSSING HEAD	EA	2		\$0.00
28	PUSH BUTTON	EA	6		\$0.00
29	EROSION CONTROL (WATTLES) (20")	LF	160		\$0.00
30	ROADWAY EXCAVATION	CY	3000		\$0.00
31	AGGREGATE BASE CLASS 2	CY	9207		\$0.00
32	STRUCTURE BACKFILL	CY	5890		\$0.00
33	PIPE REINFORCED CONCRETE, CLASS IV, 36"	LF	1278		\$0.00
34	INSTALL 22.5° FACTORY FITTED WYE CONNECTION 36" RGRCP	EA	1		\$0.00
35	CONSTRCT HEADWALL PER COB STD DTL 51200.	EA	2		\$0.00
36	PAVEMENT MARKING (WHITE EXTRUDED THERMOPLASTIC)(0.090")	LF	15750		\$0.00
37	PAVEMENT MARKING (YELLOW EXTRUDED THERMOPLASTIC)(0.090")	LF	17250		\$0.00
38	PAVEMENT MARKING (TRANSVERSE) (THERMOPLASTIC) (ALKYD) (0.090")	LF	605		\$0.00
39	PAVEMENT LEGEND (EXTRUDED THERMOPLASTIC)(ALKYD)(0.090")	EA	10		\$0.00
40	PAVEMENT SYMBOL (EXTRUDED THERMOPLASTIC)(ALKYD)(0.090")	EA	25		\$0.00
41	OBLITERATE PAVEMENT MARKING (ARROW SYMBOL OR LEGEND)	EA	18		\$0.00
41A	OBLITERATE PAVEMENT MARKING (STRIPE)	LF	340		\$0.00
42	TYPE "D" RPMs SPACING YELLOW MARKERS	LF	865		\$0.00
43	TYPE "G" RPMs SPACING WHITE MARKERS	LF	370		\$0.00
44	NEW SIGN PANEL	EA	7		\$0.00
45	REMOVE AND RELOCATE SIGN	EA	9		\$0.00
46	REMOVE TRAFFIC SIGNALS	LS	1		\$0.00
47	INSTALL SIGN POST	EA	18		\$0.00
48	INSTALL SIGN POST FOUNDATION	EA	18		\$0.00
49	POLE (SPECIAL)(APS ARCHITECTURAL SQUARE TUBE WITH 8X8 MAST ARM)	EA	13		\$0.00
50	FOUNDATION (APS ARCHITECTURAL SQUARE TUBE)	EA	13		\$0.00
51	ELECTRICAL CONDUIT (2 1/2") (PVC)	LF	3930		\$0.00
52	PULL BOX (CONTRACTOR INSTALLED)(APS FURNISHED)	EA	13		\$0.00
53	CONDUCTORS (ROADWAY LIGHTING)	LS	1		\$0.00
54	LUMINAIRE (LED)(250W HPS EQUIVALENT)	EA	13		\$0.00
55	PROTECT EXISTING WATER/SEWER LINES	LF	75		\$0.00
56	INSTALL RIP RAP 12" DEPTH PER SHT 25 DETAIL B	SF	240		\$0.00
57	INSTALL AREA INLET PER SHT 25 DETAIL C	EA	1		\$0.00
58	SHOTCRETE	SY	1426		\$0.00
59	INTERNALLY ILLUMINATED SIGNS	EA	4		\$0.00
60	MOBILIZATION/DEMobilIZATION	LS	1		\$0.00
61	TRAFFIC CONTROL ALLOWANCE	LS	1	\$40,000.00	\$40,000.00
62	APS ALLOWANCE	LS	1	\$150,000.00	\$150,000.00
63	OWNER'S CONTINGENCY	LS	1	\$150,000.00	\$150,000.00
			TOTAL CONSTRUCTION COST		\$340,000.00